

# **Ground and Flight Testing of Non-Chrome Paint Systems; Part 1–Acceleration Factors**

W.H. Abbott

Battelle-Columbus

Air Force Corrosion Managers Conference

Robins AFB, GA.

16-18 August 2011

Report Documentation Page				Form Approved OMB No. 0704-0188	
Public reporting burden for the collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to a penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.					
1. REPORT DATE <b>AUG 2011</b>		2. REPORT TYPE		3. DATES COVERED <b>00-00-2011 to 00-00-2011</b>	
4. TITLE AND SUBTITLE <b>Ground and Flight Testing of Non-Chrome Paint Systems; Part 1-Acceleration Factors</b>				5a. CONTRACT NUMBER	
				5b. GRANT NUMBER	
				5c. PROGRAM ELEMENT NUMBER	
6. AUTHOR(S)				5d. PROJECT NUMBER	
				5e. TASK NUMBER	
				5f. WORK UNIT NUMBER	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) <b>Battelle-Columbus,505 King Avenue,Columbus,OH,43201-2696</b>				8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)				10. SPONSOR/MONITOR'S ACRONYM(S)	
				11. SPONSOR/MONITOR'S REPORT NUMBER(S)	
12. DISTRIBUTION/AVAILABILITY STATEMENT <b>Approved for public release; distribution unlimited</b>					
13. SUPPLEMENTARY NOTES <b>Presented at the 2011 Air Force Corrosion Conference held 16-18 Aug 2011 at Robins AFB, GA. U.S. Government or Federal Rights License</b>					
14. ABSTRACT					
15. SUBJECT TERMS					
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT <b>Same as Report (SAR)</b>	18. NUMBER OF PAGES <b>16</b>	19a. NAME OF RESPONSIBLE PERSON
a. REPORT <b>unclassified</b>	b. ABSTRACT <b>unclassified</b>	c. THIS PAGE <b>unclassified</b>			

# Basis of Study


- Provide Supporting Data on Performance of Wide Range of Non-Chrome or Reduced Chrome Paint Stackups for Decisions Regarding Chrome Elimination
- Evaluate Wide Range of Chemical Stresses/Threats To Coatings
- Emphasis on Corrosion In Severe Ground and Flight Environments – **Field Data**
- Evaluate Significance of A Severe Ground Exposure to Flight; i.e. **Acceleration Factors (This Briefing)**
- Accelerated Laboratory Corrosion Tests Do Not Match Field and May Give Total Reversals of Performance

Field, 1 Yr; Poor NC Primers

- ASTM B117
- GM9540
- G2



KC135 Wing Skin



2024 T3 Al

# Overview

- A Large Flight and Ground Exposure Study Is Being Conducted To Evaluate Non-Chrome Paint Stackups In Comparison To Standard Chromated Systems
- The Emphasis is **Corrosion** as Produced By a Variety of Physical, Chemical, and Biological Stresses
  - Atmospheric/Coastal/Daytona Beach – This Briefing
  - Flight on OML of military aircraft – This Briefing
  - Fungal
  - Decon Solutions
  - Biocides
  - Urine
  - Wash Intervals
  - Wash Intervals + Biocides

# Scope and Approach In Study

- >60 Paint Systems Under Evaluation on Ground At Battelle's Daytona Beach Exposure Site
  - Mix and match pretreatments, primers, and topcoats
  - Painted and Scribed **Corrosion Sensors** (Electrical/Quantitative)
  - Painted and Scribed 2024 T3 **Aluminum Panels** (Visual/Subjective)
  - Painted and Scribed **Galvanic Couples** (Steel/Al) (Visual/Subjective)
- 9 Paint Systems Being Flown on Painted and Scribed Corrosion Sensors On Upper Fuselage of 42 Aircraft (Initiated by OSD)
  - C130
  - C5
  - HC144

# Examples of Ground and Flight



Daytona Test Rack @ 50 Meters  
(1 of 3 in use; ESI Steel =  
165,000 microgm/cm2/yr.




Galvanic Samples; 1 Year; Ground



Panel with 6 sensors on C130; Upper Fuselage

Quantitative/  
Objective

Visual/  
Subjective




Typical sensor and Panel



# Examples of Appearance of Field Samples



Best NC/NC Coating  
4+ Years; 2024 Al




Typical Chromate Coating  
4+ Years; 2024 Al



Poor NC Coating  
<1 Year; 2024 Al



Galvanic Test Samples  
< 1 Year; 2024 Al/Steel




Galvanic with Poor  
NC Coating; < 1 Year



KC135 Wing Skin  
2+ Years; C/C and NC Coatings

# Current Fleet Basing vs Worldwide Environmental Severity Index (ESI) Distribution



Ground Severity = Accelerated Exposure vs. Most of US Military Land Basing



# Paint Stackups For Flight and Ground Evaluations – 2007 and 2009 Start

## 2009 Long Term Start; Ground and C130, C5, HC144


- ID=1 Alumigold / 44GN098 (DEFT) / 99GY001 (DEFT)
- ID=2 Alumigold / AE2100 (XP406-110) ANAC / 99GY001(DEFT)
- ID=3 Alodine 5700 / 02GN084 (DEFT) / 99GY001 (DEFT)
- ID=4 Alodine 5700 / 16708TEP (Hentzen) / 99GY001 (DEFT)
- ID=5 Prekote / Sicopoxy 577-630 (ANAC) / 99GY001 (DEFT) C130 only
- ID=5 Prekote / 02Y040B (DEFT) / 99GY001 (DEFT) C5 only
- ID=6 DEFT 1015/3021 / 02GN093 (DEFT) / 99GY001 (DEFT) C130 ,HC144 only
- ID= 6a Prekote / 02Y040B (DEFT) / PPG Desothane HS Half of C5s only
- ID = 6b Prekote / 02Y040B (DEFT) / AE5000 (ANAC) Half of C5s only

	MIL-PRF-85285 Ty IV
	MIL-PRF-85285 Ty I
	MIL-PRF-23377 CI C2
	MIL-PRF-23377 CI N
	MIL-PRF-85582 CI N
	MIL-DTL-81706


## 2007 Long Term Start – Ground and flight (H60/P3/AH64A)

- ID=7 Alodine 1200S / 02GN083 (DEFT) / 99GY001 (DEFT)
- ID=8 Prekote / AE2100 (first generation) / AE5000 (ANAC) Old System 2
- ID=9 Prekote / 02Y-040 (DEFT) / 03GY310 (DEFT) Old System 3
- ID=10 MIL-C-5541 / 02Y040 (DEFT) / 03GY310 (DEFT) Old System 4
- ID=11 Alodine 5200 / Sicopoxy / 03GY310 (DEFT)
- ID=12 Prekote / Americoat 3351 / 03GY310 (DEFT)

# Summary of Sensor Results – Ground @ Daytona For Same Paint Systems As C130 Flight




## Combined Data For Ground and On-Aircraft (Solid Lines = Ground; Points=Flight By T/N)



# Significance of Data

- Paint Systems Are Degrading Faster In Severe Environment of Daytona Than On OML of Aircraft
- This Provides Some Degree of Realistic Acceleration = AF 1
- Painted aluminum on ground will take much longer to visual degradation than response of sensor = AF 2

# Example of Acceleration Factor For Painted and Scribed Sensor In Flight vs. Daytona Beach Exposure -- One Paint System



# Analysis of Ground vs. Flight Data

- Ground is Accelerated vs Flight Per Sensor Data
  - ESI on OML is less than at Daytona for worst case basing of probably all USAF fleets
  - Analysis does not apply to sea basing
- 2024 AI Panels (Visual) React Much Slower Than Sensors = Additional Acceleration For Sensors Data
  - Acceleration Factor Even Greater
- Same Order of Performance of Paint Stackups For Both – Sensor vs.AI (Gnd) and Sensor Gnd vs Flight
- Enough Data to Define **Approximate** Acceleration Factors



# Acceleration Factors Gnd vs Flight and Gnd Sensor vs Gnd 2024 AI

- Sensors By Paint Stackup; Time (days) to Reach Same Electrical Change (Delta = 0.1 V)

	» Ground	Flight	Factor	AI (Visual)	Factor
— ID=1	180	400	2.2	670	3.7
— ID=2	>600	>700	----	---	
— ID=3	120	461	3.8	>720	>6
— ID=4	170	420	2.3	710	4.1
— ID=5	170	322	1.9	680	4
— ID=6	310	461	1.1	560	1.8
— MgRP (2007)	670	> 1500		>1500	
— Cr/Cr (2007)	980	> 1500		>1500	
		»	Av= 2.3		

# Acceleration Factor (Cont'd)

- Painted and Scribed 2024 AI Panels Require 2-4 Times Longer To Reach Visible Degradation Compared to Sensor Results
- Conservative Estimate = 4:1 Acceleration Factor For Severe Ground (Sensor) vs. Flight (2024 AI) For Worst Case Land Based Assets
- Significance of Sensor Results vs Painted 2024
  - Systems Deployed In 2007 Exposed to Equivalent of >10 Years On Wing of C130 and C5
  - Large Matrix Started 2009 Now Exposed to Equivalent of ~8 Years On Wing of C130 and C5

# Conclusions

- Procedures and Protocols Established For Flying Multiple Painted Corrosion Sensors on OML of Aircraft
- Approximate Acceleration Factors Now Established To Estimate The Meaning of Ground Based Exposures to Current ESI Levels of Fleet Basing
- Data Are Giving Optimistic Appraisals For Long Term Corrosion Protection For The Best Non-Chrome Systems For USAF Aircraft.
- Studies Are Continuing To Define Acceleration Factors More Precisely